

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
1. Public Land Survey	T 6N R 10W L-4
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 SEP 13 PM 12:06  
REG. OF DEEDS  
*Lucy Standa*

9372

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on July 29, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-4 1831---GLO---Not Set  
1978---LCRC #1110---Bonnama---Set Capped Rerod on E-W 1/4 line 2660.5' West of E 1/4 corner per Williams & Works records.  
10" Ash WSW 16.24' 14" Oak WNW 28.79' 8" Oak NNE 12.94'  
12" Oak SE 0.40' E-W wire fence is South 4'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/25/96  
CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-4 Found Capped Rerod in root of tree per the following witnesses:  
12" Ash WSW 16.2' 18" Oak WNW 28.6' 8" Stump NNE 13'  
12" Oak SE 0.4' Wire fence E-W is South 4'

Said Capped Rerod is 0.2' N and 0.3' E. from intersection of 1/4 lines and agrees with survey information by others.

The Capped Rerod is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-4 Rerod with "Kent.Co. Remon." cap in tree root (leaning Westerly)  
Spike and tag N. side 12" Oak S60°E 0.38'  
Spike and tag NW side 12" Ash S60°W 16.22'  
Set Nail & KC Remon. tag S. side 18" Oak N70°W 28.57'  
Set Nail & KC Remon. tag W. side 22" Oak N05°E 40.87'  
East-West fence is South 4'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/25/96