

**SURVEY &  
REMONUMENTATION**

FEB 14 1997

COMMISSION KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T <u>6N</u> R <u>10W</u>	<u>L-7</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 MAR 20 AM 8:47

REG. OF DEEDS

*Lucy Bond*

8998

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7	1831	GLO	Mullett	Set Post
	1964	Kent Co. Wit.		1" Iron
	1978	LCRC #4414	VanKooten	1/2" Round Iron
	1978	LCRC #1309	Jonker	1/2" Round Iron
	1982	LCRC #2753	Merdzinski	Set Kent County Monument
	1991	LCRC #6055	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/2/96  
CHAIRMAN *Harry Hubel*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/22/82 and was recorded per LCRC #2753

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron inside a 1" Iron he found. Both Irons check with Kent Co. Wit. and LCRC's #1141, 1309.

<u>LCRC #2753</u>	<u>LCRC #6055</u>
Nail/tag 24" Maple N65°W 92.10'	Nail/tag 32" Maple N72°W 91.89'
Nail/tag 28" Maple North 58.81'	Nail/tag 40" Maple North 58.80'
Nail/tag 16" Cherry N45°E 26.59'	Nail/tag 22" Cherry N47°E 26.62'
Nail/tag 10" Walnut N80°E 79.95'	Nail/tag 16" Walnut N74°E 79.88'
Nail/tag 10" Hickory S25°E 29.02'	Nail/tag 12" Hickory S14°E 29.08'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Standard Kent County Monument

Nail & KC Remon. tag SW side	34" Maple	N72°W	91.89'
Nail & KC Remon. tag W. side	42" Maple	North	58.80'
Nail & KC Remon. tag SE side	24" Cherry	N47°E	26.66'
New Nail & KC Remon. tag S. side	18" Walnut	N74°E	79.94'
Nail & KC Remon. tag E. side	14" Hickory	S14°E	29.08'

C/L B.T. road is 1.3'± South and corner is on fence line North



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96