

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>10W</u> | <u>L-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:47
REG. OF DEEDS
David S. Bond

8999

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Stake
	1972	LCRC #321	Spicer	PK Nail
	1982	LCRC #2754	Merdzinski	Set Kent County Monument
	1991	LCRC #6056	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 3/26/82 and was recorded per LCRC #2754

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the PK Nail he found. Said PK Nail checks with Kent Co. Wit. and LCRC #321.

<u>LCRC #2754</u>	<u>LCRC #6056</u>
Nail/tag 16" Hickory N65°E 76.33'	Nail/tag 20" Hickory N60°E 76.16'
Nail/tag 14" Maple S45°E 65.60'	Nail/tag 22" Maple S45°E 65.90'
Nail/tag P. Pole S05°W 45.83'	Nail/tag P. Pole S03°W 45.86'
C/L steel fence post North 49.50'	Nail/tag 6" Elm N08°W 49.04'
C/L pavement is South 1.0'	C/L pavement is South 1.2'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Standard Kent County Monument

Nail & KC Remon. tag SE side 24" Hickory	N60°E	76.20'
Nail & KC Remon. tag SW side 24" Maple	S45°E	65.87'
Nail & KC Remon. tag W. side P. Pole	S03°W	45.86'
New Nail & KC Remon. tag E. side 10" Elm	N08°W	49.06'

C/L pavement (Cascade Rd.) is South 1'±
On fence & brush rows N-S



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96