

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:	Corner Code #
T 6N R 10W	L-11
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:47

REG. OF DEEDS

W. J. Bond

9000

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Witnesses given
	1974	LCRC #709	Spicer	1/2" Iron
	1981	LCRC #1896	Merdzinski	Set Kent County Monument
	1991	LCRC #6057	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harrison

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 5/19/81 and was recorded per LCRC #1896

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron over a 3" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #709.

LCRC #1896	LCRC #6057
Nail/tag 24" Ash S68°E 79.87'	Nail/tag 16" Hickory S05°E 39.34'
Nail/tag CP Pole S33°E 70.68'	Nail/tag 34" Hickory S68°E 79.85'
Nail/tag 14" Hickory S05°E 39.38'	Nail/tag P. Pole S33°E 70.65'
Nail/tag P. Pole S70°W 178.97'	Nail/tag P. Pole S72°W 178.90'
C/L Rd. is South 2.5'±	C/L blacktop (52nd St.) is South 2.5'±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument	
New Nail & KC Remon. tag W. side 18" Hickory	S05°E 39.35'
New Nail & KC Remon. tag N. side 36" Ash	S68°E 79.85'
Nail & KC Remon. tag NE side P. Pole	S33°E 70.73'
Set Nail & KC Remon. tag N. side P. Pole	S75°W 182.88'
Set Nail & KC Remon. tag S. side 10" Elm	N65°E 50.79'
C/L blacktop road (52nd St.) is South 2.5'±	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/1/96