

FEB 14 1997

COMMISSION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>10W</u>	<u>L-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:47  
 REG. OF DEEDS  
*Lucy Bond*

**9001**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1831	GLO	Mullett	Set Post
	1974	LCRC #722	Vankooten	1" Round Iron
	1978	LCRC #1137	Vankooten	Square Spike
	1982	LCRC #2843	Jonker	Set Kent County Monument
	1991	LCRC #6058	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 4/28/82 and was recorded per LCRC #2843.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Round Iron he found. Said Round Iron checks with Kent Co. Wit. and LCRC #1137

<u>LCRC #2843</u>	<u>LCRC #6058</u>
Nail/tag 18" Oak S40°W 68.74'	Nail/tag 22" Oak S40°W 68.78'
Nail/tag 4" Elm S35°E 75.55'	Nail/tag 10" Elm S35°E 75.42'
Nail/tag P. Pole N60°E 120.0'	Nail/tag Tw. 20" Oak S00°E 46.84'
Sq. Spike 14" Oak N00°W 81.57'	Nail/tag 18" Oak N00°E 81.70'
Sq. Spike 18" Oak S00°W 46.81'	C/L 60th St. is South 1'±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard Kent County Monument

Nail & KC Remon. tag NW side 24" Oak	S40°W	68.78'
Nail & KC Remon. tag SW side 12" Elm	S35°E	75.42'
Nail & KC Remon. tag W. side Twin 20" Oak	S00°E	46.86' (dead)
Nail & KC Remon. tag W. side 18" Oak	N00°E	81.73' (dead)
Set Nail & KC Remon. tag S. side P. Pole	N70°E	179.65'
C/L Asph. Rd. E-W (60th St.) is South 1'±		



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 3/1/96