

**SURVEY &
REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>10W</u> | <u>M-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

56 MAR 20 AM 8:48

REG. OF DEEDS
Eric Standa

9004

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 12, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1831	GLO	Mullett	Set Post
	1967	Kent Co. Wit.		1" Iron
	1974	LCRC #698	Spicer	1" Iron
	1981	LCRC #1897	Merdzinski	Set Kent County Monument
	1991	LCRC #6062	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN *Harry Stuber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 5/19/81 and was recorded per LCRC #1897

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the PK Nail over 3/4" Iron he found over remains of a Conc. Mon. All check with Kent Co. Wit. and LCRC #698.

LCRC #1897 (Nail/tag in trees, etc.) LCRC #6062
20" Hick. N10°E 90.04' 10" B'wood N85°E 86.63' same witnesses as
12" Walnut S15°E 83.16' LCRC #1897 ±
C/L top fence post S40°W 55.44'
"+" in conc. culv. S75°W 67.04'
"+" in conc. culv. N65°W 72.16'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 Standard Kent County Monument
- | | |
|--|------------------------------|
| New Nail & KC Remon. tag W. side 20" Walnut | S15°E 83.32' |
| Nail & KC Remon. tag top C/L fence post | S41°W 55.40' |
| New Nail & KC Remon. tag W. side 26" Hickory | N24°E 89.94' |
| Nail & KC Remon. tag S. side 12" Basswood | N81°E 86.53' |
| "X" cut on S. end conc. culv. | S83°W 67.08' |
| "X" cut on N. end conc. culv. | N65°W 72.22' |
| Kent Co. Mon. (A-5, T6N, R9W) | North 28.25' |
| C/L N-S road is West 0.5'± | C/L road West is North 4.5'± |
| Tree row East is 25'± North | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96