

SURVEY & REMONUMENTATION

MAY 28 1997

**KENT COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in
KENT COUNTY

(County)

Located In: Corner Code #

1. Public Land Survey	T6N	R10W	M-12
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 JUN -7 AM 8:28
REG. OF DEEDS
[Signature]
9174
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12	1831	GLO	Mullett	Set Post
	1978	LCRC #1137	Vankooten	"Common" (witnesses given)
	1981	LCRC #1993	Jonker	Set Kent County Monument
	1991	LCRC #6068	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/14/81 and was recorded per LCRC #1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3" Round Pipe he found. Said Round Pipe checks with LCRC #1137

<u>LCRC #1993</u>		<u>LCRC #6068</u>	
Nail/tag 18" Oak	S00°W 34.92'	Nail/tag 9" Elm	S35°E 55.35'
Nail/tag Tri. 28" Oak	S88°E 36.51'	Nail/tag Tri. 16" Oak	S85°E 36.52'
Nail/tag Tw. 18" Oak	N90°W 18.27'	Nail/tag Tw. 16" Oak	S88°W 48.92'
Nail/tag 8" Elm	S32°E 55.27'	Nail/tag 8" Pine	S49°W 52.21'
		Nail/tag Ser. Pole	N52°E 57.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

M-12 Standard Kent County Monument	
Nail & KC Remon. tag NE side 12" Elm	S35°E 55.37'
Nail & KC Remon. tag S. side Tri. 18" Oak	S85°E 36.52'
New Nail & KC Remon. tag S. side Twin 18" Oak	S88°W 48.98'
New Nail & KC Remon. tag SE side 12" Pine	S49°W 52.24'
PK Nail & KC Remon. tag NW side Serv. Pole	N52°E 57.68'
C/L N-S grav. rd. is East 7'±	
In line with tree & fence rows E-W	



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 4/12/96