

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC -5 AM 8:52

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N	R 11W	A-1
	T 7N	R 11W	A-13
	T 6N	R 12W	M-1
	T 7N	R 12W	M-13
2. Property Controlling in Section	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____

William R. Byl
REG. OF DEEDS

7594

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on March 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-1 1831 GLO Lyon Set Post P.A. 345 1930 KENT COUNTY
City of Grand Rapids City Iron PEER APPROVED 12/1/94
Williams & Works City Iron CHAIRMAN *Henry Huber*
1982 LCRC #2933 Bonnema PK Nail
1984 LCRC #4042 Byl Set Steel Bar & "KENT CO. REMON." cap
The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/30/84 and was recorded per LCRC #4042.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found Steel Bar (1/2" x 6") with "KENT CO. REMON." cap per witnesses from above LCRC as set by William R. Byl in place of the PK Nail he found. Said PK Nail checks remaining witnesses and survey data by others.

LCRC #4042

Nail & tag E. side traffic signal pole	S45°E	56.86'
Nail & tag N. side traffic signal pole	N45°W	51.91'
SW cor. brick veneer of building	N55°E	75.45'
NW cor. foundation of building	S15°E	118.15'
NE cor. foundation of building	S45°W	44.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Steel Bar and "KENT CO. REMON." cap		
Nail & tag E. side traffic signal pole	S45°E	56.76'
Nail & tag N. side traffic signal pole	N45°W	51.98'
SW cor. brick veneer of building	N55°E	75.40'
NW cor. foundation of building	S15°E	119.17'
NE cor. foundation of building	S45°W	44.86'



Signed by *William R. Byl*
Surveyor's Michigan License No. 23502

Date 11 27 94