

SEP 18 1995
\$7.00
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 MAY 12 AM 10:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Lucy J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 6N R 11W A-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

8351A

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on March 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5	1831	GLO	Mullett	Set Post
	1920-64	Williams & Works		"X" cut - mon. box - PK Nail
	1931	City of Grand Rapids		City Iron - "X" cut
	1984	LCRC #3975	Byl	Set Kent Co. Mon.
	1989	LCRC #4741	Beuche	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 9/10/84 and was recorded per LCRC #3975

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found Standard (Harrison) Kent Co. Mon. per information from above LCRC as set by William R. Byl as described in above LCRC.

LCRC #3975 & #4741

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/30/95
CHAIRMAN *Kirk Breitels*

See sketch reverse side for information.
Found 4 reference irons to be intact along with corresponding witnesses

The selected position is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

A-5 Standard Kent County Monument

See sketch reverse side



Signed by *Kirk Breitels* Date 3/30/95
Surveyor's Michigan License No. 30077

The 4 reference irons are set with sufficient accuracy so as to eliminate the need to occupy or measure to the corners in 28th Street. Any of the 4 irons can be occupied by theodolite, and an azimuth can be obtained from either (or both) adjacent irons. Coordinates of the section corners can then be calculated from the bearings and distances shown.

