

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE 94 DEC -5 AM 8:52
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In: Corner Code =#

- | | | |
|------------------------------------|------------|-----|
| 1. Public Land Survey | T 6N R 11W | A-7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

W. J. Bond
REG. OF DEEDS

7599

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Oct. 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7	1831	GLO	Mullett	Set Post
	1900-67	Williams & Works		"X" cut-Mon. Box
	1980	City of Wyoming		Mon. Box
	1984	LCRC #3949	Byl	Set 1/2 Rod with "KENT CO. REMON." cap
	1988	LCRC #4731	Bueche	1/2" Rod with "KENT CO. REMON." cap

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/12/84 and was recorded per LCRC #3949

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found 1/2" Rod with "KENT CO. REMON." cap in per witnesses from above LCRC as set by William R. Byl in mon. box. Said position in Mon. Box (found empty) checks with remaining witnesses and survey data by others.

<u>LCRC #3949</u>		<u>LCRC #4731</u>	
NE cor. bldg. fdn.	S60°W 60.52'	same witnesses as LCRC #3949	
S'yly cor. conc. sign base	N45°W 98.34'		
SW bolt of sign base	S40°E 70.48'		
"V" cut face light pole	N30°E 75.13'		
KC Mon.	N00°E 13.43'		

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry P. P...*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Standard Kent County Monument			
NE cor. brick bldg.	S60°W	60.45'	
S'yly cor. conc. school sign base	N45°W	98.53'	
SW bolt of sign base	S40°E	70.48'	
"V" cut face light pole	N30°E	75.13'	
KC Mon. (NE cor. Sec. 24, T6N, R12W)	N00°E	13.43'	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94