

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:52

COMMISSION

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T 6N R 11W	A-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

W. J. Bond
REG. OF DEEDS

7600

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Oct. 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8	1831	GLO	Not Set	P.A. 345 1990 KENT COUNTY
	1929-65	Williams & Works	Mon. Box	PEER APPROVED 12/11/94
	1980	City of Wyoming	Mon. Box	CHAIRMAN <i>Harry Huber</i>
	1984	LCRC #3907	Byl	Set Kent County Monument
	1988	LCRC #4732	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/2/84 and was recorded per LCRC #3907

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1" Iron Pipe he found in a Mon. Box. Said 1" Iron Pipe in Mon. Box checks with City of Wyoming witnesses and survey data by others
LCRC #3907 LCRC #4732

SW cor. porch fdn. Hse. #4006	N40°E	75.64'	same witnesses as LCRC #3907
SW cor. conc. step Hse. #4010	N70°E	54.63'	
NW cor. fndn. Hse. #4014	S75°E	63.79'	
NW cor. concrete bldg.	S30°E	103.85'	
C/L top fire hydrant	S60°W	39.81'	
KC Mon. (E 1/4 cor. 24-6-12)	N00°W	22.32'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Standard Kent County Monument in mon. box			
SW cor. porch fdn. Hse. #4006	N40°E	75.64'	
SW cor. conc. step Hse. #4010	N70°E	54.63'	
NW cor. fndn. Hse. #4014	S75°E	63.74'	
NW cor. concrete bldg.	S30°E	103.85'	
C/L top fire hydrant	S60°W	39.78'	
SE cor. brick "Burger King" sign	N15°W	157.65'	
KC Mon. (E 1/4 Sec. 24-6-12)	N00°W	22.32'	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94