

# SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:52

COMMISSION

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code -##

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>11W</u> | <u>A-9</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |

*W. R. Byl*  
REG. OF DEEDS

7601

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Oct. 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |     |         |                  |         |   |
|-----|---------|------------------|---------|---|
| A-9 | 1831    | GLO              | Mullett | Set Post                                |
|     | 1911-39 | Williams & Works |         | Stake-Stones-Gas Pipe-Monument          |
|     |         | Kent Co. Wit.    |         | Mon. Box                                |
|     | 1980    | City of Wyoming  |         | Mon. Box                                |
|     | 1984    | LCRC #3950       | Byl     | Set 1/2" Rod with "KENT CO. REMON." cap |
|     | 1988    | LCRC #4733       | Bueche  | 1/2" Rod in Mon. Box                    |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/9/84 and was recorded per LCRC #3950

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 Found 1/2" Rod with "KENT CO. REMON." cap in mon. box per witnesses from above LCRC as set by William R. Byl in place of the Iron Pipe he found in a mon. box. Said Iron Pipe in mon. box checks with remaining witnesses and measurements by others

- |                             |                   |                              |
|-----------------------------|-------------------|------------------------------|
| <u>LCRC #3950</u>           | <u>LCRC #4733</u> |                              |
| Nail & tag W. sd. P. Pole   | N40°W 81.72'      | same witnesses as LCRC #3950 |
| SW cor. (middle) bldg. fdn. | N65°E 88.24'      |                              |
| NW cor. bldg. fdn.          | S60°E 85.57'      |                              |
| C/L MBT Manhole             | S50°W 64.60'      |                              |
| Kent Co. Mon.               | N00°E 30.99'      |                              |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/1/94  
CHAIRMAN *Stanley Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |     |   |       |         |
|-----|---|-------|---------|
| A-9 | 1/2" Rod with "KENT CO. REMON." cap in mon. box |       |         |
|     | Nail & KC Remon. tag W. sd. P. Pole             | N40°W | 81.72'  |
|     | SW cor. (middle) bldg. fdn.                     | N65°E | 88.27'  |
|     | C/L MBT Manhole                                 | S50°W | 64.74'  |
|     | NE cor. conc. base elec. box                    | S35°W | 74.10'  |
|     | NW cor. brick bldg.                             | S40°E | 114.01' |
|     | Kent Co. Mon. (NE Sec. 25, T6N, R12W)           | N00°E | 31.02'  |



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11/27/94