

# SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 27 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:53

For corner in COMMISSION  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T	6N	R	11W	A-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*W. J. Bond*  
REG. OF DEEDS

7602

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Oct. 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-10	1831	GLO		Not Set
	1923-66	Williams & Works		Iron in Mon. Box
	1939	Kent Co. Wit.		Iron in Mon. Box
	1984	LCRC #3908	Byl	Set Kent County Monument
	1987	LCRC #4518	Herrema	Reset Kent County Monument after const.
	1988	LCRC #4734	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/1/94  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/2/84 and was recorded per LCRC #3908

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1" Iron he found in a mon. box. Said 1" Iron in mon. box checks with Kent Co. Wit. and measurements by others.

<u>LCRC #3908</u>		<u>LCRC #4734</u>	KC Mon. (M-10 6-12)	N00°E	0.99'
Nail & tag 30" Oak	S30°W	78.13'	Nail & Remon. tag 34" Oak	N86°W	62.56'
SE face Lt. Pole	N45°W	50.33'	C/L top hydrant	N15°W	109.52'
NW cor. brick bldg.	S60°E	86.21'	SE'ly cor. 1'x 12' brk. sign	S27°W	127.21'
C/L top hydrant	N50°E	47.38'	PK & Remon. tag SE cor. CB	S30°E	60.18'
Face of curb	S00°W	22.18'	C/L top hydrant	N42°E	54.10'
			NE cor. conc. around MH	S40°W	18.26'
			Nail & Remon. tag P. Pole	S70°W	41.02'
			NW cor. 10'x 12.5' conc.	S30°E	62.97'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-10 Standard Kent County Monument	
New Nail & Remon. tag S. sd. 36" Oak	N86°W 62.56'
C/L top hydrant	N15°W 109.52'
SE'ly cor. 1'x 12' brk. sign	S27°W 127.21'
PK nail & Remon. tag in asph. at SE cor. CB	S30°E 60.18'
C/L top hydrant	N42°E 54.10'
NE cor. conc. around MH	N40°W 18.26'
Nail & Remon. tag SE sd. P. Pole	S70°W 41.02'
NW cor. 10'x 12.5' conc. covered by asph.	S30°E 62.97' m/1
KC Mon. (E 1/4 cor. Sec. 25-6-12)	N00°E 1.00'



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 112794