

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:53

For corners **COMMISSION**
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Lucy J. Bond
REG. OF DEEDS

7603

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Oct. 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the regulations of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1969 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Huber*

- | | | | | |
|------|---------|------------------|----------|--|
| A-11 | 1831 | GLO | Mullett | Set Post |
| | 1911-72 | Williams & Works | | Stake-Boat Spike-Mon. Box |
| | 1972 | LCRC #132 | Chambers | 1" Iron in mon. box |
| | 1980 | City of Wyoming | | 1" Iron in mon. box |
| | 1984 | LCRC #3951 | Byl | Set 1/2" Rod with "KENT CO. REMON." cap- |
| | 1987 | LCRC #4514 | Herrema | Set Kent Co. Mon. after const. |
| | 1988 | LCRC #4735 | Bueche | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/9/84 and was recorded per LCRC #3951

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Donald L. Herrema after road construction in same location as William R. Byl set 1/2" Rod with "KENT CO. REMON." cap in place of 1" Iron Pipe he found in a mon. box. Said 1" Iron Pipe in mon. box checks with City of Wyoming and LCRC #132.

<u>LCRC #3951</u>	<u>LCRC #4514 (#4735 same witnesses)</u>		
SW cor. conc. blk. bldg.	N45°E 117.26'	PK nail & remon. tag P. Pole	N39°W 50.30'
NW cor. brick bldg.	S25°E 153.54'	PK nail & remon. tag P. Pole	S23°W 116.85'
C/L top hydrant	N60°E 63.20'	SE cor. of bricks on bldg.	N46°W 121.31'
Face of sign post	N40°W 83.12'	NW cor. of bricks on bldg.	S36°E 153.58'
Face 1' dia. vent pipe	S55°W 82.52'	SW cor. block bldg.	S36°E 153.61'
Kent Co. Mon.	S00°W 27.10'	C.I. Mon. at NE cor. 36-6-12	S55°E 117.20'
		South	27.10'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11 Standard Kent County Monument
- | | | |
|--|-------|---------|
| PK nail & remon. tag E. side P. Pole | N39°W | 50.30' |
| PK nail & remon. tag E. side P. Pole | S23°W | 116.82' |
| SE cor. of bricks on bldg. | N46°W | 121.31' |
| NW cor. of bricks on bldg. | S36°E | 153.58' |
| SW cor. block bldg. | N55°E | 117.30' |
| Capped Re-rod | S40°W | 76.29' |
| Kent Co. Mon. (NE cor. Sec. 36, T6N, R12W) | S00°W | 27.10' |



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94