

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>B-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 DEC 20 AM 8:39  
REG. OF DEEDS  
*W. J. Bond*

**8800**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Nov. 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

B-2	1831	GLO	Not Set
	1901	Williams & Works	No desc. or witnesses
	1927	Williams & Works	City Iron
	1931	City of Grand Rapids	City Iron

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-2 Did not find anything at corner nor do any witnesses remain. Established location from street improvements and adjoining plats. Fits measurements of others. Said location is 0.4' W. & 0.4' S. from true intersection of 1/4 lines.

The location as established above is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN Harry Huber

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-2 Set Standard Kent County Monument per "B" above.

NW corner bldg. foundation	N90°W	33.00'
SW corner bldg. foundation	S10°W	130.67'
Set Nail & KC Remon. tag E. side P. Pole	S20°E	101.64'
NW face steel billboard post	S45°E	54.48'
SE corner brick bldg.	N75°E	152.58'
SW corner brick bldg. (garage)	N70°E	84.85'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 12/11/95