

**SURVEY & REMONUMENTATION**  
 KENT COUNTY REMONUMENTATION

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 94 DEC -5 AM 8:54

For corners in **COMMISSION**

KENT COUNTY <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>C-1</u>
	T <u>7N</u> R <u>11W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. R. Byl*  
 REG. OF DEEDS

7612

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on July 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1990 KENT COUNTY

C-1	1831	GLO	Mullett	Set Post	PEER APPROVED 12/1/94
	1930,1956	City of Grand Rapids	Byl	City Iron	<i>Harry Huber</i>
	1984	LCRC #3918	Bueche	Set Kent County Monument	
	1988	LCRC #4671		Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/21/84 and was recorded per LCRC #3918

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the City Iron he found. Said City Iron checks with City of Grand witnesses that remain and adjoining plats.

<u>LCRC #3918</u>	<u>LCRC #4671</u>
Nail & tag E. sd. P. Pole	N20°W 97.24'
Nail & tag E. sd. P. Pole	S35°W 58.57'
NW cor. brk. ven. Bldg. #1204	S60°E 106.54'
SW cor. conc. pad @ back wk.	N45°E 46.10'
	plus
	SE cor. C.B. header S55°E 5.97

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument	
Nail & KC Remon. tag E. side P. Pole	N20°W 97.24'
Nail & KC Remon. tag NW side P. Pole	S35°W 58.60'
NW cor. brick veneer Bldg. #1204	S60°E 106.54'
SE cor. C.B. header	S55°E 54.94
NE cor. C.B. header	N40°E 51.85



Signed by *W. R. Byl*  
 Surveyor's Michigan License No. 23502

Date 11/27/94