

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:54

For corners in
KENT COUNTY

	Located In:	Corner Code #/
(County)		
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Eric J. Bond
REG. OF DEEDS

7613

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2	1831	GLO	Mullett	Set Post	P.A. 345 1980 KENT COUNTY
	1910-50	Williams & Works		City Iron	PEER APPROVED <u>12/1/94</u>
		City of Grand Rapids		City Iron	CHAIRMAN <i>Harry Huber</i>
		Kent Co. Wit.		City Iron	
	1984	LCRC #3912	Byl	Set Kent County Monument	
	1992	LCRC #6494	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/2/84 and was recorded per LCRC #3912

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the City Iron he found. Said City Iron checks with Williams & Works and Kent Co. Wit.

<u>LCRC #3912</u>	<u>LCRC #6494</u>	
SE cor. bldg. fdn.	N55°W 65.45'	same witnesses as LCRC #3912
NW cor. bldg. fdn.	S20°E 121.45'	
C/L NE bolt sign base	S65°W 37.08'	plus
Nail & tag Telegr. Pole	N55°E 81.88'	
Nail & tag P. Pole	S15°E 72.88'	NE cor. brick bldg. S10°W 173.83'
		C/L S'yly of 2 RR tracks N. 114' m/1

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 Standard Kent County Monument	
SE cor. bldg. fdn.	N55°W 65.40'
NW cor. bldg. fdn.	S20°E 121.42'
C/L NE bolt of sign base	S65°W 37.11'
Nail & KC Remon. tag S. side Telegraph Pole	N55°E 81.82'
NE cor. brick bldg.	S10°W 173.90'
Nail & KC Remon. tag SE side Power Pole	S30°W 76.13'
C/L S'yly of 2 RR tracks N. 114' m/1	



Signed by *W. R. Byl* Date 11/27/94

Surveyor's Michigan License No. 23502