

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code -#
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:55

Eric J. Bond
REG. OF DEEDS

7623

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William R. Byl, in a field survey on Sept. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94
CHAIRMAN *Harry Huber*

C-12	1831	GLO	Mullett	Set Post
	1974	LCRC #707	Bonnema	3/4" Iron
	1982	LCRC #2996	Byl	Set Kent County Monument
	1992	LCRC #6504	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/20/82 and was recorded per LCRC #2996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 3/4" Iron Pipe he found. Said Iron Pipe checks with LCRC #707.

<u>LCRC #2996</u>		<u>LCRC #6504</u>	
Nail & tag P. Pole	S85°E 36.50'	Nail & KC Remon. tag S. side PP	S85°E 36.50'
SE cor. gar. fdn.	N45°W 109.14'	SE cor. gar. fnd. Hse. #781	N45°W 109.14'
NE cor. gar. fdn.	S40°W 130.55'	NE cor. gar. fnd. Hse. #5619	S40°W 130.55'
NW cor. brk. planter	S40°E 79.17'	NW cor. brick planter	S40°E 79.17'
		NW cor. of header of CB	N17°W 82.56'
		NE cor. of header of CB	N17°E 80.11'
		On C/L Bit. Rd. N-S-W	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument

Nail & KC Remon. tag S. side P. Pole	S85°E 36.58'
SE cor. gar. fnd. Hse. #781	N45°W 109.14'
NE cor. gar. fnd. Hse. #5619	S40°W 130.55'
NW cor. brick planter	S40°E 79.20'
NW cor. of header of CB	N17°W 82.56'
NE cor. of header of CB	N17°E 80.11'
On C/L Bit. Rd. N-S-W	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94