

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:55

William R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T 6N R 11W	D-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

7625

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1	1831 GLO	Not Set
	1909, 1931 City of Grand Rapids	PEER APPROVED 12/1/94
	1905-11 Williams & Works	CHAIRMAN <i>Harry Hubert</i>
	1985 LCRC #4265	City Iron
	1988 LCRC #4675	City Iron
	Byl	Set Kent County Monument
	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 1/10/85 and was recorded per LCRC #4265

P.A. 345 1990 KENT COUNTY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the City Iron he found. Said City Iron checks with City of Grand Rapids, Williams & Works and adjoining plats.

<u>LCRC #4265</u>		<u>LCRC #4675</u>	
Face of hydrant jacket at grade	N15°W	22.66'	same witnesses as LCRC #4265
SE cor. brick planter	N60°W	78.06'	
NE cor. brick porch pillar	S55°W	72.96'	
Nail & tag S. sd. traf. sig. pole	S25°W	20.00'	
Nail & tag W. sd. Power Pole	N65°E	69.36'	
Kent Co. Mon. S 1/4 Sec. 32	N90°E	41.04'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Standard Kent County Monument			
Face of hydrant jacket at grade	N15°W	22.66'	
SE cor. brick planter	N60°W	78.08'	
NE cor. brick porch pillar	S55°W	72.96'	
Nail & tag S. side Traffic Signal Pole	S25°W	20.04'	
Nail & tag W. side Power Pole	N65°E	69.36'	
Kent Co. Mon. S 1/4 Sec. 32, T7N, R11W	N90°E	41.04'	



Signed by *William R. Byl* Date 112794
Surveyor's Michigan License No. 23502