

\$7.00
\$2.00

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	R	11W	D-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

Lucy Board

95 DEC 20 AM 8:38

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8802

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Kirk Breitels, in a field survey on Nov. 17, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-4 1831 GLO Not Set
 City of Grand Rapids City Iron
 "X" in walk North 29.0' Gas Pipe South 33.06'
 1948-53 Williams & Works City Iron
 Kent Co. Wit. Iron in pavement
 Fence Post South 33.35' T.P. NE 51.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Found City Iron in C/L Alger St. E-W. Measure South to Iron Pipe 33.2' and South to fence post 33.32'. Fits measurements of others and adjoining plats. Said City Iron is 2.5' E. & 2.3' S. from true intersection of 1/4 lines.

The City Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-4 Set Standard Kent County Monument in place of the City Iron

Face of fence post	S00°E	33.32'
NE corner brick house #1164	S10°W	60.23'
NE corner foundation house #2406	S60°W	98.31'
SW corner foundation house #1173	N35°E	72.49'
SE corner foundation house #1163	N30°W	75.76'
Set Nail & KC Remon. tag side P. Pole	N25°E	24.59'



Signed by

Kirk Breitels

Date

12/11/95

Surveyor's Michigan License No. 30077