

JAN 24 1996

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	D-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 DEC 20 AM 8:39

REG. OF DEEDS
8812

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Nov. 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-6 1831 GLO Not Set
1935-56 Williams & Works Iron
MH South 58.7'
Kent Co. Wit. Iron
14" Oak NW 27.65' 16" Oak N. 23.9' F.P. NE 21.68'
12" Oak SE 14.25' Db1. Oak SSW 39.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


D-6 Found 2" Iron Pipe that fits witnesses to face ("V" cuts) of trees per Kent Co. Wit. and Williams & Works. Iron fit measurements and angles from adjoining plats. Said Iron is 0.1' N. & 0.9' E. from true intersection of 1/4 lines.

The 2" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN Harry Kubers

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-6 Set Standard Kent County Monument in place of the 2" Iron Pipe
Set Nail & KC Remon. tag W. side 30" Oak N35°W 27.97'
Set Nail & KC Remon. tag E. side 40" Oak N05°W 23.88'
Set Nail & KC Remon. tag NE side 36" Oak S45°E 14.62'
Set Nail & KC Remon. tag W. side 40" Oak S15°E 40.15'
C/L Manhole S00°E 58.79'
Set Nail & KC Remon. tag N. side 36" Poplar S60°W 31.52'



Signed by Kirk Breitels Date 12/11/95
Surveyor's Michigan License No. 30077