

# SURVEY & REMONUMENTATION

APR 27 1995

## COMMISSION

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 DEC -5 AM 8:56

*Lee J. Bond*  
REG. OF DEEDS

7630

Register of Deeds Stamp & File Number

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>D-11</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-11	1831	GLO	Mullett	Set Post	
	1938	Kent Co. Wit.		Concrete Monument	
	1976	LCRC #939	Merdzinski	1 1/2" Iron	
	1982	LCRC #3001	Byl	Set Kent County Monument	
	1987	LCRC #4512	Milliron	Reset Kent County Monument	
	1992	LCRC #6510	Bueche	Kent County Monument	

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/11/94  
CHAIRMAN *Harry Stube*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/20/82 and was recorded per LCRC #3001

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


D-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Rex Milliron from witnesses used in 1982 by William R. Byl when he set a Kent County Monument in place of the 1 1/2" x 3" Iron Pipe he found over a Concrete Monument. Said Iron Pipe and Concrete Monument checks with Kent Co. Wit. and LCRC # 939.

<u>LCRC #3001</u>	<u>LCRC #6510</u>	
Nail & tag P. Pole	N00°W 43.41'	SE cor. gar. fnd. #1185 N25°W 89.77'
SE cor. gar. fnd. hse. #1185	N20°W 89.76'	KC Remon. tag & nail W. sd. PP North 43.35'
SE cor. brick hse. #1213	N55°E 130.58'	PK E. sd. 26" Ash N30°E 65.18'
NW cor. brick hse.	S45°E 147.16'	SW cor. brick bldg. N40°E 105.35'
		PK E. root 38" Maple S40°W 71.90'
		NW cor. hse. #1212 (brick) S35°W 147.06'
		On C/L Bit. Rd. E-W; C/L Bit. Rd. S. is E. 24'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-11 Standard Kent County Monument			
SE cor. gar. fnd. #1185	N25°W	89.77'	
KC Remon. tag & nail W. side P. Pole	N00°E	43.42'	
Set KC Remon. tag & nail E. side 30" Ash	N30°E	65.22'	
SW cor. brick bldg.	N40°E	105.35'	
PK F. root 38" Maple	S40°W	71.90'	
NW cor. hse. #1212 (brick)	S35°W	147.06'	
On C/L Bit. Rd. E-W; C/L Bit. Rd. S. is E. 24'			



Signed by *W. R. Gyl* Date 112794

Surveyor's Michigan License No. 23502