

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC -5 AM 8:56

W. R. Byl
 REG. OF DEEDS

For corners in
KENT COUNTY
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

7635
 Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on July 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1902-47	Williams & Works		City Iron	PEER APPROVED 12/1/94
	1931	City of Grand Rapids		City Iron	CHAIRMAN <i>Harry Huber</i>
	1933	Kent Co. Wit.		Iron	
	1984	LCRC #3767	Byl	Set Kent County Monument	
	1992	LCRC #6514	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 2/13/84 and was recorded per LCRC #3767

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the City Iron he found next to a stone and old axe head. Said City Iron checks with Williams & Works, City of Grand Rapids and Kent Co. Wit.

<u>LCRC #3767</u>	<u>LCRC #6514</u>
Nail & tag 18" Oak N55°W 23.60'	same witnesses as LCRC #3767
Nail & tag 8" Oak N05°E 43.90'	
Nail & tag 18" Oak N70°E 39.56'	plus
Nail & tag 18" Cherry S70°E 57.35'	
N. edge N'ly sidewalk, Alger St. connector S20°W 44.10'	Nail & KC Remon. tag W. sd. 8" Oak N20°W 32.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 Standard Kent County Monument

Nail & KC Remon. tag S. side 22" Oak	N55°W	23.62'
Nail & KC Remon. tag E. side 12" Oak	N05°E	43.95'
Nail & KC Remon. tag N. side 22" Oak	N70°E	39.58'
Nail & KC Remon. tag N. side 20" W. Cherry	S70°E	57.52'
Nail & KC Remon. tag W: sd. 8" Oak	N20°W	32.15'
"V" cut N. edge N'ly sidewalk, Alger St. connector 60' m/l E'ly from light pole #9	S20°W	44.19'



Signed by *W. R. Byl* Date 11/27/94
 Surveyor's Michigan License No. 23502