

**SURVEY & REMONUMENTATION**

KENT COUNTY REMONUMENTATION

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:56

For corners in **COMMISSION**  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>E-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. R. Byl*  
REG. OF DEEDS

**7642**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Sept. 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-11	1831	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		Iron in mon. box
	1976	LCRC #939	Spicer	Iron in mon. box
	1982	LCRC #2991	Byl	Set Kent County Monument in mon. box
	1992	LCRC #6521	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 7/27/82 and was recorded per LCRC #2991

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94  
CHAIRMAN *W. R. Byl*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1" x3" Iron he found inside a mon. box. Said Iron in mon. box checks with Kent Co. Wit. and LCRC #939.

LCRC #2991	LCRC #6521
NE cor. conc. curb	S45°W 63.65'
SE cor. conc. sign base	N45°W 68.34'
Nail & tag MBT Pole	S45°E 51.01'
Nail & tag Traffic Signal Pole	N60°E 51.37'
	NE cor. concrete curb
	S45°W 63.56'
	SE cor. concrete sign base
	N45°W 68.34'
	Nail & KC tag N. side Traffic Signal Pole
	N60°E 51.66'
	SW cor. brick bldg. #5180
	N40°E 141.66'
	NW cor. brick bldg. #1616
	S50°E 113.93'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Standard Kent County Monument	
NE cor. concrete curb	S45°W 63.60'
SE cor. concrete sign base	N45°W 68.34'
Nail & KC Remon. tag N. side Traffic Signal Pole	N60°E 51.66'
SW cor. brick bldg. #5180	N40°E 141.66'
NW cor. brick bldg. #1616	S50°E 113.98'
C/L top of hydrant	S45°W 62.07'

Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11/27/94

