

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 8:57

W. J. Bond
REG. OF DEEDS

7645

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>F-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|-----------|----------------------|--------|--------------------------|
| F-1 | 1831 | GLO | | Not Set |
| | 1925-47 | Williams & Works | | Iron-City Iron |
| | 1930,1956 | City of Grand Rapids | | City Iron |
| | 1981 | LCRC #2482 | Glaza | Iron |
| | 1985 | LCRC #4263 | Byl | Set Kent County Monument |
| | 1988 | LCRC #4673 | Bueche | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/9/85 and was recorded per LCRC #4263

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the City Iron he found. Said City Iron checks with Williams & Works, City of Grand Rapids and LCRC #2482.

LCRC #4263

- SW cor. brick veneer Hse. #1961 N35°W 89.70'
- NE cor. brick veneer Hse. #1954 S45°W 81.84'
- NE cor. brick veneer Hse. #1958 S10°W 63.83'
- Face of hydrant jacket at grade N65°W 53.57'
- Kent Co. Mon. at S 1/4 Sec. 31 N90°E 38.91'

LCRC #4673

same witnesses as LCRC #4263

P.A. 945 1990 KENT COUNTY

PEER APPROVED 12/1/94


CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Standard Kent County Monument

- | | | |
|---|-------|--------|
| SW cor. brick veneer Hse. #1961 at grade | N35°W | 89.74' |
| NE cor. brick veneer Hse. #1954 at grade | S45°W | 81.84' |
| NE cor. brick veneer Hse. #1958 at grade | S10°W | 63.92' |
| Face of hydrant jacket at grade | N65°W | 53.57' |
| Kent Co. Mon. at S 1/4 Sec. 31, T7N, R11W | N90°E | 38.97' |



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94