

JAN 24 1996

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	R	11W	F-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Section	S		T	R	

REG. OF DEEDS

*Eric J. Bond*

95 DEC 20 AM 8:38

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

8803

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on March 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-4	1831	GLO	Not Set
	1901-11	Williams & Works	Fence corner
	1930	Williams & Works	Used point 131.42' E. of E. line
			"Walgarth Plat"
	1939-59	Williams & Works	City Iron
		Kent Co. Wit.	City Iron

P.A. 346 1950 KENT COUNTY  
 PEER APPROVED 3/30/99  
 CHAIRMAN Harry Steuber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


F-4 Did Not find anything at corner. Per "Indian Village No. 4," (Liber 61, Pg. 9) the Center of Section 9 is 459.45' West of the Northwest corner Lot 197 - being the place of beginning of said plat. Established the location of the Center of Section 9 from irons along the E-W 1/4 line, also being the North line of Lots 197-199 of said plat as well as the North line of "Breton Plat" (Liber 61, Pg. 17). Position of corner falls very near the back corner of the garage to house #2365 Okemos Dr (Lot 209, "Indian Village No. 4"). Said location is 0.5' S. and 0.4' W. from true intersection of 1/4 lines.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-4 No monument set at this corner.

SEE LCRC # 8804 FOR LOCATION OF WITNESS MONUMENT



Signed by *Kirk Breitels*

Date 12/11/95

Surveyor's Michigan License No. 30077