

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

JAN 24 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

| For corners in KENT COUNTY (County) | Located In: | Corner Code # |
|---|-------------------------|---------------|
| 1. Public Land Survey | T 6N R 11W | F-6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REG. OF DEEDS

Lucy Bond

95 DEC 20 AM 8:39

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8811

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Kirk Breitels, in a field survey on Nov. 15, 1994,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-6 1831 GLO Not Set 1920-62 Williams & Works Iron
15" Maple ESE 67.74' 14" Maple SE 44.49'
P. Pole SW 25.64' 8" Maple SW 44.93'
- 1961 Kent Co. Wit. 1" Iron
CP WSW 44.33' CP SE 49.25'
- 1977 LCRC #1038 Bonnema 1" Iron
C/L top hydr. SSE 35.49' P. Pole SSW 26.23'
24" Maple ESE 68.42' Guy Pole NW 49.83'
- 1987 Exxel Iron per LCRC #1038 1988 William R. Byl Iron per LCRC #1038

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Found PK Nail in C/L E-W road (32nd St. road construction approx. 1990). Fits remaining witnessess of those above. Said PK Nail is 7.1' N. & 17.7' W. from true intersection of 1/4 lines and fits measurements by others.

The PK Nail is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-6 Set Standard Kent County Monument in place of the PK Nail.
- SE corner brick pillar N60°W 78.86'
- C/L chain link fence post N40°E 63.65'
- Set Nail & KC Remon. tag W. side P. Pole S10°W 26.23'
- Set Nail & KC Remon. tag E. side 27" Maple S30°E 45.26'
- C/L top of fire hydrant S00°E 35.49'



Signed by

Kirk Breitels

Date

12/11/95

Surveyor's Michigan License No.

30077