

**SURVEY & REMONUMENTATION**

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC -5 AM 8:57

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                    |   |    |   |     |      |
|------------------------------------|---|----|---|-----|------|
| 1. Public Land Survey              | T | 6N | R | 11W | F-11 |
|                                    | T |    | R |     |      |
|                                    | T |    | R |     |      |
|                                    | T |    | R |     |      |
| 2. Property Controlling in Section | S |    | T | R   |      |
|                                    | S |    | T | R   |      |
| 3. Miscellaneous Property in Sec.  | S |    | T | R   |      |
|                                    | S |    | T | R   |      |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

*W. R. Byl*  
REG. OF DEEDS

7650

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Sept. 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-11	1831	GLO	Mullett	Set. Post
	1972	LCRC #176	Spicer	1/2" Iron
	1974	LCRC #648	VanKooten	Iron in mon. box
	1982	LCRC #3003	Byl	Set Kent County Monument
	1992	LCRC #6528	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/1/94  
CHAIRMAN *Harry Shuler*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/24/82 and was recorded per LCRC #3003

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1/2" Rerod he found. Said 1/2" Rerod checks with LCRC #176. No evidence of mon. box or witnesses per LCRC #648 - recorded incorrectly ???

<u>LCRC #3003</u>		<u>LCRC #6528</u>
SE cor. brick gar. N55°W	138.75'	same witnesses as LCRC #3003
SE cor. brick hse. N05°W	73.65'	
SW cor. fnd. hse. N25°E	114.50'	plus
Nail & tag P. Pole N00°W	36.18'	
Nail & tag P. Pole S00°W	26.17'	SW cor. conc. porch to hse. #1995 N30°W 82.92'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Standard Kent County Monument		
SE cor. brick garage to hse. #1991	N55°W	138.72'
SE cor. brick hse. #1997	N05°W	73.69'
SW cor. fnd. hse. #2011	N25°E	114.44'
SW cor. conc. porch to hse. #1995	N30°W	82.92'
Set Nail & KC Remon. tag E. side P. Pole	S05°W	37.32'
Set Nail & KC Remon. tag W. side P. Pole	N00°E	40.09'



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11/27/94