

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE 94 DEC -5 AM 8:57

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

W. J. Bond
REG. OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7652

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1	1831	GLO	Mullett	Set Post
	1907-47	Williams & Works		Pt. 52.14' W. of
	1927	City of Grand Rapids		Iron
	1985	LCRC #4262	Byl	Set Kent County Monument
	1988	LCRC #4672	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/3/85 and was recorded per LCRC #4262

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl. Location was established from adjoining plats and other data, 52.14' West of SE cor. Sec. 33, T7N, R11W.

LCRC #4262	LCRC #4672
Face of 4" steel traf. signal pole	Face of 4" steel traffic signal pole,
S40°W 42.41'	2' above grade S40°W 42.53'
Face of hydr. jacket N60°W 43.23'	C/L MBT manhole S65°W 57.03'
C/L MBT manhole S65°W 56.87'	Nail & tag S. side P. Pole N40°W 25.27'
Nail & tag P. Pole N40°W 25.27'	Nail & tag E. side P. Pole N45°E 74.75'
KC Mon. SE cor. Sec. 33 N90°E 52.14'	KC Mon. at SE cor. Sec. 33 N90°E 52.24'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Standard Kent County Monument	
Face of 4" steel traffic signal pole, 2' above grade	S40°W 42.53'
C/L MBT manhole	S65°W 57.03'
Set Nail & KC Remon. tag SW side P. Pole	N40°W 29.28'
Set Nail & KC Remon. tag SE side P. Pole	N45°E 76.18'
KC Mon. at SE cor. Sec. 33, T7N, R11W	N90°E 52.24'



Signed by *W.R. Byl*
Surveyor's Michigan License No. 23502

Date 112794