

**SURVEY & REMONUMENTATION**

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:58

*W. R. Byl*  
REG. OF DEEDS

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**7663**  
Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Sept. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12	1831	GLO	Mullett	Set Post
	1961	Kent Co. Wit.		No desc. of cor. - witnesses given
	1974	LCRC #648	VanKooten	1" Iron at fence cor.
	1982	LCRC #3165	Jonker	1" Iron at fence cor.
	1983	LCRC #3387	Stadt	Set Kent County Monument
	1992	LCRC #6540	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/1/94  
CHAIRMAN *Harry Stuber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 5/4/83 and was recorded per LCRC #3387

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the 1" Iron he found. Said 1" Iron checks with Kent Co. Wit. and LCRC's #648 & #3165

<u>LCRC #3387</u>	<u>LCRC #6540</u>
Nail & tag 16" Ash S80°W 20.77'	Nail & KC Remon. tag S. sd. 20" Ash S80°W 20.77'
Nail & tag 12" Ash South 13.33'	Nail & KC Remon. tag W. sd. 14" Ash South 13.33'
Nail & tag 8" Ash N30°W 32.74'	Nail & KC Remon. tag W. sd. 24" Oak N15°E 22.16'
Nail & tag 22" Oak N15°E 22.20'	SE cor. fnd. to hse. #5594 Discovery Dr.
1" Solid bar 2' tall at steel fence post North 0.50'	N65°W 77.33'
	At cor. of yard fence N & W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Standard Kent County Monument			
New Nail & KC Remon. tag S. sd. 22" Ash	S80°W	20.74'	
New Nail & KC Remon. tag W. sd. 14" Ash	S00°E	13.43'	
Nail & KC Remon. tag W. sd. 27" Oak	N15°E	22.16'	
SE cor. fnd. to hse. #5594 Discovery Dr.	N65°W	77.28'	
NE cor. gar. fnd. #5594 Discovery Dr.	N40°W	106.11'	
At cor. of yard fence N & W			



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11/27/94