

JAN 24 1996 KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T	6N	R	11W	H-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REG. OF DEEDS

95 DEC 20 AM 8:39

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8810

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Nov. 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-6 1831 GLO Not Set
- 1929-77 Williams & Works Set Iron at "X" 1/4 lines-Boat Spike-RR Spike
- 12" Hickory SW 90.0' 12" Maple NNE 26.35'
- 12" Maple NE 53.3' T.P. SSE 17.85'
- 1972 LCRC #325 Spicer RR Spike
- CP Pole N20°E 47.76' NE cor. brick hse. S30°E 103.05'
- 16" Ash S10°W 27.14' 20" Maple N70°E 67.23'
- Exxel Eng. Used per LCRC #325
- 1980 William R. Byl, Inc. RR Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-6 Found RR Spike in C/L Asph. road. Fits remaining witnesses of those above. Said RR Spike is 0.6' S. & 1.6' W. from true intersection of 1/4 lines and fits measurements by others.

The RR Spike is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN Harry Huber

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-6 Set Standard Kent County Monument in place of the RR Spike
- Set Nail & KC Remon. tag E. side MBT Pole S00°E 18.21'
- Set Nail & KC Remon. tag E. side P. Pole N20°E 48.90'
- SE corner 2' x 2' brick planter N35°W 80.21'
- Set Nail & KC Remon. tag N. side 24" Hickory S75°E 90.45'
- NE corner brick house S30°E 103.02'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 12/11/95