

**SURVEY & REMONUMENTATION**

APR 27 1995

**COMMISSION**

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:58

*W. R. Byl*  
REG. OF DEEDS

7667

Register of Deeds Stamp & File Number

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William R. Byl, in a field survey on Sept. 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-7	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1972	LCRC #323	Spicer	3/4" Iron
	1982	LCRC #3000	Byl	Set Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/12/99  
CHAIRMAN Fanny Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/19/82 and was recorded per LCRC #3000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 3/4" Iron Pipe he found alongside a stone. Said Iron checks with LCRC #323 and survey data by others.

LCRC #3000

Nail & tag E. side 6" Ash	S50°E	81.89'
Nail & tag E. side 6" Oak	N33°E	20.74'
Nail & tag E. side 10" Oak	N45°W	10.44'
Nail & tag S. side 12" Oak	N75°W	20.20'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument

New Nail & KC Remon. tag E. side 12" Ash	S50°E	81.90'
New Nail & KC Remon. tag E. side 10" Oak	N33°E	20.73'
Nail & KC Remon. tag E. side 14" Oak	N45°W	10.46'
New Nail & KC Remon. tag S. side 14" Oak	N75°W	20.23'
Set Nail & KC Remon. tag N. side 16" Oak	S85°W	36.54'



Signed by *W. R. Byl* Date 112794  
Surveyor's Michigan License No. 23502