

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	R	11W	H-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	
4. Lot No. _____, Recorded Plat _____					
5. Private Claims _____					

REG. OF DEEDS

Lucy Standa

95 DEC 20 AM 8:40

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8818

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Nov. 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-8	1831	GLO		Not Set
	1941-72	Williams & Works		Fence corner
	1961	Kent Co. Wit.		Iron
		18" Oak ENE 5.82'	24" Maple SE 11.58'	
	1972	LCRC #323	Spicer	Set Iron at fence corner
		12" Ash N90°E 18.68'	24" Maple S90°W 7.50'	16" Oak N80°W 3.70'
	1980	William R. Byl, Inc.		"T" Iron per LCRC #323
		Exxel Eng.		Iron per LCRC #323

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-8 Found "T" Iron per LCRC #323. Said "T" Iron is 10.6' E. & 1.2' N. from true intersection of 1/4 lines and agrees with previous survey data by others.

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN Harry Huber

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-8	Set Standard Kent County Monument	in place of the	"T" Iron
	Set Nail & KC Remon. tag N. side	18" Ash	N90°E 18.63'
	Set Nail & KC Remon. tag W. side	36" Maple	S05°W 7.72'
	Set Nail & KC Remon. tag S. side	24" Oak	N85°W 8.97'
	Set Nail & KC Remon. tag E. side	12" Ash	N00°E 27.48'
	On remains of fence to N-S-W		



Signed by Kirk Breitels

Date 12/11/95

Surveyor's Michigan License No. 30077