

\$7.00
\$2.00

JAN 24 1996 KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	H-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 20 AM 8:40
REG. OF DEEDS
Eric Bond
8823
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on March 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-10 1831 GLO Not Set
 1948-68 Williams & Works Set and used Iron at "X" 1/4 lines
 18" Tulip Tr. NE 24.5' 15" Hickory NW 58.6' Tri. 10" Cherry SW 24.6'
 1972 LCRC #110 Bonnema Iron-Fits 1959 wits. & CP Co. wits.
 12" Tw. Maple SE 54.52' 14" Ash E. 28.60'
 P. Pole NW 34.06' Iron N. 1.7'
 Exxel Eng. Iron per LCRC #110

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/30/95
 CHAIRMAN *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Found Iron Pipe per LCRC #110 witnesses. Said Iron Pipe is 1.9' S. & 0.1' W. from true intersection of 1/4 lines and fits measurments by others.

The Iron Pipe per LCRC #110 is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10 Set Standard Kent County Monument in place of the Iron Pipe
 Set Nail & KC Remon. tag N. side 27" Ash S90°E 28.49'
 Set Nail & KC Remon. tag NW side P. Pole N35°W 34.14'
 E'ly face of 4" steel Lt. Pole S80°W 70.54'
 Set Nail & KC Remon. tag E. side Tw. 15" Elm N40°E 51.49'
 Set PK Nail top of N. guard rail post S10°E 62.18'
 Iron Pipe - North 1.7'



Signed by *[Signature]*
 Surveyor's Michigan License No. 30077

Date 12/11/95