

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:58

Lucy Bond
REG. OF DEEDS

7669

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 11W	H-11
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		1" Iron
	1955	CP Co.		Boat SPIKE
	1971	LCRC #51	Chambers	Boat Spike
	1984	LCRC #3765	Byl	Set Kent County Monument
	1991	LCRC #6192	McCloskey	Reset Kent County Monument after const.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 2/15/84 and was recorded per LCRC #3765

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by J. Patrick McCloskey at the same location as set in 1984 by William R. Byl in place of the Boat Spike he found over the top of a 1/2" iron. Said Boat Spike & Iron checks with Kent Co. Wit., CP Co., and LCRC #51.

<u>LCRC #3765</u>		<u>LCRC #6192</u>	
C/L MBT Manhole	S55°E 84.10'	E. cor. 3' sq. conc. base traf. pole	S22°W 70.40'
C/L Gas Manhole	S10°E 26.25'	NE cor. brick chimney	N34°W 109.36'
SE cor. fnd. hse.	N45°E 104.00'	SW cor. bottom step	N54°W 119.10'
Nail & tag Guy Pole	S55°W 38.69'	N. cor. 3' sq. conc. base traf. pole	N50°E 85.31'
Nail & tag P. Pole	N50°E 63.12'	Nail & tag E. side Guy Pole	S34°W 61.87'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 Standard Kent County Monument			
E. cor. 3' sq. conc. base traffic light pole	S22°W	70.40'	
NE cor. brick chimney	N34°W	109.36'	
SW cor. bottom step	N54°W	119.10'	
N. cor. 3' sq. conc. base traffic light pole	N50°E	85.31'	
Nail & KC Remon. tag E. side Guy Pole	S34°W	61.87'	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 112794