

\$7.00
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|----|---|-----|------|
| 1. Public Land Survey | T | 6N | R | 11W | H-12 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | R | | |
| | S | | R | | |
| 3. Miscellaneous | S | | R | | |
| Property in Section | S | | R | | |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 20 AM 8:40
REG. OF DEEDS
8830
Register of Deeds Stamp & File Number

| A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | |
| 3 | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | |
| 5 | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | |
| 7 | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | |
| 9 | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | |
| 11 | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | |
| 13 | | | | | | | | | | | |

I, Kirk Breitels, in a field survey on Dec. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-12 1831 GLO Not Set
 1929-48 Williams & Works Fence Corner
 1959 Kent Co. Wit. Iron
 18" Hickory ESE 133.50' 36" Elm SSW 52.8' 18" Tw. Ash NW 37.7'
 1960 Williams & Works Held true N-S 1/4 line found Fence Cor. to be 1' E.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/11/94
 CHAIRMAN Harry J. Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-12 Established intersection of 1/4 lines and found Fence Corner (N-E-W) per Williams & Works to be 1.4'± East of true N-S 1/4 line and 0.5'± N. of true E-W 1/4 line. Found Iron per Kent Co. Wit. to be 0.6'± W. and 0.3'± S. of intersection of 1/4 lines. Do not have any knowledge of origin of the Iron per Kent Co. Wit. or any information of its use in surveys.

The intersection of the 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-12 Set Standard Kent County Monument at the intersection of the 1/4 lines of Sec. 34.
 Set Nail & KC Remon. tag W. side 15" Oak N25°E 4.41'
 Set Nail & KC Remon. tag E. side 10" Oak S35°E 14.27'
 Set Nail & KC Remon. tag W. side 30" Oak N25°W 52.50'
 Set Nail & KC Remon. tag W. side 10" Oak N05°W 54.94'
 Set Nail & KC Remon. tag SW side Tw. 30" Ash N45°W 38.81'
 Set Nail & KC Remon. tag NW side 24" Poplar S35°W 51.26'
 On N'y edge of small stream



Signed by Kirk Breitels

Date 12/11/95

Surveyor's Michigan License No. 30077