

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -5 AM 8:58

Tim J. Jand
 REG. OF DEEDS

For corners in
KENT COUNTY
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7670

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Aug. 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Stone
		LCRC #51	Chambers	1" Iron
1981		LCRC #1690	Merdzinski	Set Kent County Monument in mon box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/1/94
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/24/81 and was recorded per LCRC #1690

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) in a mon. box per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron over a 3/4" Iron he found inside a mon. box. Both Irons check with Kent Co. Wit. and LCRC #51.

LCRC #1690

Nail & KC Remon. tag W. side 24" Basswood	North	46.55'
Nail & KC Remon. tag NE side 8" Elm	S55°W	91.11'
SW cor. to hse. fnd. #2815	N35°E	128.53'
SE cor. to hse. #2815	N50°E	154.44'
SW cor. Conc. Dr. to hse #2815	N75°E	130.34'
NW cor. shed (frame)	S20°W	99.53'

Iron in Mon. Box East 10.54'; On fence South; On tree line & fence North
 C/L blktp. rd. (60th St.) E-W is 2' South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument in mon. box

New Nail & KC Remon. tag W. side 30" Basswood	N00°E	46.55'
SW cor. to hse. fnd. #2815	N35°E	128.53'
SE cor. to hse. #2815	N50°E	154.44'
SW cor. Conc. Dr. to hse #2815	N75°E	130.34'
NW cor. shed (frame)	S20°W	99.53'
Set Nail & KC Remon. tag SE side P. Pole	S40°W	58.74'
Kent Co. Mon. in Mon. Box N 1/4 cor. Sec. 3-5-11	S90°E	10.54'

On fence South; On tree line & fence North
 C/L blktp. rd. (60th St.) E-W is 2' South



Signed by *W. R. Byl*
 Surveyor's Michigan License No. 23502

Date 11/27/94