

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 8:58
Lee J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7676

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on Sept. 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1831	GLO	Mullett	Set Post	
	1966	Kent Co. Wit.		Iron	
	1972	LCRC #273	VanKooten	"T" Iron	
	1981	LCRC #2032	Hackbardt	Set Kent County Monument	
	1989	LCRC #4950	Bueche	Kent County Monument	
	1993	LCRC #6753	Roon	Kent County Monument	

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Huben*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 7/6/81 and was recorded per LCRC #2032

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #273.

<u>LCRC #2032 & 4950</u>	<u>LCRC #6753</u>	
C/L hydrant	N50°W 51.18'	Nail & tag P. Pole S25°E 71.67'
NW cor. CB header	N80°E 55.26'	Nail & tag P. Pole S65°W 56.41'
C/L manhole	N90°E 15.60'	Nail & tag Guy Pole N35°E 65.50'
SE cor. CB header	S75°W 48.46'	Nail & tag P. Pole N45°W 51.78'
C/L manhole	N30°W 31.84'	
Face of fence post	S50°E 69.55'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument	
C/L hydrant	N50°W 51.14'
NW cor. CB header	N80°E 55.26'
C/L manhole	N90°E 15.56'
SE cor. CB header	S75°W 48.34'
C/L manhole	N30°W 30.85'
Face of fence post	S50°E 69.84'
New Nail & KC Remon. tag W. side P. Pole	S25°E 71.40'
New Nail & KC Remon. tag SE side P. Pole	S55°W 56.41'
New Nail & KC Remon. tag NW side Guy Pole	N35°E 65.42'
New Nail & KC Remon. tag NE side P. Pole	N45°W 51.81'



Signed by *William R. Byl* Date 11/27/94
Surveyor's Michigan License No. 23502