

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 8:58

W. R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>11W</u>	I-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7678

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on Sept. 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94
CHAIRMAN Harry Huber

I-9	1831	GLO	Mullett	Set Post
	1953	Kent Co. Wit.		Iron in mon. box
	1981	LCRC #2037	Hackbardt	Set Kent County Monument
	1982	LCRC #3189	Wickham	Reset Kent Co. Mon. after road const.
	1989	LCRC #4953	Bueche	Kent County Monument
	1993	LCRC #6764	Roon	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 8/27/81 and was recorded per LCRC #2037

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found standard Kent Co. Mon. (Harrison) inside a mon. box per witnesses from above LCRC as set by Burt Wickham Jr. in the same location as set in 1981 by Glen S. Hackbardt in place of the 3/4" x 18" crimped iron he found inside a mon. box. Said crimped iron checks with Kent Co. Wit. and survey data by others.

<u>LCRC #3189</u>	<u>LCRC #4963 & 6764</u>	
N15°W Nail & tag CP Pole 76.86'	Cut mark @ back of curb	N70°W 36.12'
N30°E Nail & tag Guy Pole 80.34'	Nail & tag Guy Pole	N30°E 76.80'
S65°W Nail & tag CP Pole 79.98'	Nail & tag CP Pole	S65°W 79.98'
S50°E Nail & tag CP Pole 79.09'	Nail & tag CP Pole	S50°E 79.09'
	Nail & tag P. Pole	N40°E 84.20'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Standard Kent County Monument in mon. box	
Cut mark @ back of curb	N70°W 36.07'
Nail & KC Remon. tag NW side Guy Pole	N30°E 76.85'
New Nail & KC Remon. tag S. side CP Pole	S65°W 80.03'
Nail & KC Remon. tag N. side CP Pole	S50°E 79.07'
Nail & MDSH tag SW side P. Pole	N40°W 84.16'



Signed by W. R. Byl
Surveyor's Michigan License No. 23502

Date 11/27/94