

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

KENT COUNTY REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE 94 DEC -5 AM 8:59
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>I-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Lewis Bond
REG. OF DEEDS

7679

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on Sept. 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: P.A. 345 1990 KENT COUNTY

- | | | | | |
|------|------|---------------|------------|--------------------------|
| I-10 | 1831 | GLO | Mullett | Set Post |
| | 1963 | Kent Co. Wit. | | Stone |
| | 1974 | LCRC #741 | Bonnema | Stone |
| | 1980 | LCRC #1430 | Merdzinski | Set Kent County Monument |
| | 1989 | LCRC #4954 | Bueche | Kent County Monument |

PEER APPROVED 12/1/94
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/16/80 and was recorded per LCRC #1430

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Stone he found. Said Stone checks with Kent Co. Wit. & LCRC #741.

LCRC #1430			LCRC #4954		
Nail & tag 24" Beech	East	24.32'	Nail & tag N. side 30" Beech	East	24.32'
Nail & tag 8" Oak	S25°W	27.70'	Nail & tag N. side 16" Hickory	West	39.50'
Nail & tag 10" Hickory	West	39.50'	Nail & tag S. side Tw. 30" Oak	N55°W	56.40'
Nail & tag Tw. 26" Oak	N55°W	56.51'	Nail & tag E. side 26" Maple	N05°E	56.63'
Nail & tag 24" Maple	N05°E	56.53'	Nail & tag W. side 22" Ash	N30°W	5.68'
Nail & tag 18" Ash	N30°W	5.68'	Nail & tag E. side 8" Ash	S20°W	18.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-10 Standard Kent County Monument
- | | | |
|--|-------|--------|
| Nail & KC Remon. tag N. side 30" Beech | S90°E | 24.32' |
| New Nail & KC Remon. tag N. side 16" Hickory | S90°W | 39.50' |
| New Nail & KC Remon. tag S. side Tw. 30" Oak | N55°W | 57.29' |
| New Nail & KC Remon. tag E. side 26" Maple | N05°E | 56.58' |
| New Nail & KC Remon. tag W. side 22" Ash | N30°W | 5.66' |
| New Nail & KC Remon. tag E. side 8" Ash | S20°W | 18.23' |
- On fence N & W



Signed by *W. R. Byl* Date 11/27/94
Surveyor's Michigan License No. 23502