

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 8:59

W. R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T <u>6N</u> R <u>11W</u>	<u>I-12</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

7681

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Sept. 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1831	GLO	Mullett	Set Post
	1972	Kent Co. Wit.	Bonnema	Stone in fence cor.
	1980	LCRC #157	Merdzinski	Stone
	1989	LCRC #1439	Bueche	Set Kent County Monument
		LCRC #4956		Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94
CHAIRMAN James Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/21/80 and was recorded per LCRC #1439

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Stone he found. Said Stone checks with Kent Co. Wit. and LCRC #157.

LCRC #1439			LCRC #4956		
Nail & tag 8" Elm	S85°E	23.33'	Nail & tag 10" Elm	S85°E	23.33'
Nail & tag Tw. 8" Ash	N82°E	138.85'	Nail & tag 12" Ash	N82°E	138.60'
Nail & tag 14" Sycamore	N52°E	123.30'	Nail & tag 18" Sycamore	N52°E	123.30'
Nail & tag 6" W. Cherry	North	53.40'	Nail & tag 8" W. Cherry	North	53.40'
Nail & tag 12" Elm	N64°W	108.93'	Nail & tag 14" Elm	N64°W	108.93'
Nail & tag fence post	South	33.04'	NW cor. garage fnd.	S20°E	117.70'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument	
New Nail & KC Remon. tag W. side 10" W. Cherry	N00°E 53.53'
NW cor. garage fnd. #3183 Paris Park	S20°E 117.84'
Set Nail & KC Remon. tag SE side 8" Oak	N30°E 43.53'
Set Nail & KC Remon. tag N. side 5" Oak	S85°E 39.02'
Iron Pipe	N00°E 37.00'
On fence line N & E; Fence W is 33' S. and 2nd fence W is 36' N	



W. R. Byl

Signed by _____ Date 11/27/94
Surveyor's Michigan License No. 23502