

**SURVEY & REMONUMENTATION**

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -5 AM 8:59

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 11W J-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*W. R. Byl*  
REG. OF DEEDS

7687

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Sept. 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94  
CHAIRMAN Harry Stubbs

- |     |      |            |           |  |
|-----|------|------------|-----------|--|
| J-9 | 1831 | GLO        | Mullett   | Set Post                               |
|     | 1976 | LCRC #951  | Bonnema   | 3/4" Iron in mon. box                  |
|     | 1981 | LCRC #2039 | Hackbardt | Set Kent County Monument in mon. box   |
|     | 1982 | LCRC #3189 | Wickham   | Reset KC Mon. in mon. box after const. |
|     | 1989 | LCRC #4961 | Bueche    | Kent County Monument                   |
|     | 1993 | LCRC #6750 | Roon      | Kent County Monument                   |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 7/6/81 and was recorded per LCRC #2039

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 1" x 18" Iron he found inside a mon. box. Said Iron checks with LCRC #951.

<u>LCRC #2039</u>		<u>LCRC #4961 &amp; #6750</u>	
Nail & tag 10" Walnut	S60°E 56.17'	"X" cut on curb	N70°W 38.03' SE cor. CB
Nail & tag 30" Sycamore	S30°W 75.21'	"X" cut on curb	S80°E 44.78' rim N35°W
Nail & tag 6" Elm	N05°W 35.33'	Cut at back of curb	N00°E 9.61' 48.78'
Nail & tag 14" Maple	S20°E 79.95'	"X" cut in curb	S75°W 32.86'
C/L Hydrant	S25°E 42.45'	Nail & tag 24" Sycamore	S30°W 75.40'
		Nail & tag 24" Cherry	South 71.38'
		"X" on manhole	N85°W 33.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-9 Standard Kent County Monument in mon. box in traffic median
- "X" cut on curb N70°W 38.03'
- "X" cut on curb S80°E 44.78'
- Cut at back of curb N00°E 9.61'
- "X" cut in curb S75°W 32.86'
- New Nail & KC Remon. tag W. side 30" Sycamore S30°W 75.39'
- New Nail & KC Remon. tag W. side 27" Cherry S05°E 71.27'
- "X" on manhole N85°W 33.40'
- SE cor. CB rim N35°W 48.73'



Signed by W. R. Byl  
Surveyor's Michigan License No. 23502

Date 11/27/94