

**SURVEY & REMONUMENTATION**

APR 27 1995

**COMMISSION**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 94 DEC -5 AM 8:59

*Wm R. Byl*  
 REG. OF DEEDS

**7688**

**Register of Deeds Stamp & File Number**

For corners in  
**KENT COUNTY**  
 (County)

Located In:	Corner Code =#
T <u>6N</u> R <u>11W</u>	<u>J-11</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William R. Byl, in a field survey on Sept. 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-11	1831	GLO	Mullett	Set Post
	1974	LCRC #741	Bonnema	"T" Iron
	1974	LCRC #768	Spicer	"T" Iron
	1982	LCRC #3002	Byl	Set Kent County Monument
	1989	LCRC #4962	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 11/21/94  
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/19/82 and was recorded per LCRC #3002

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of a 6" "T" Iron inside a 1 1/2" Iron Pipe he found over top a wire and conc. monument. Both Irons and conc. mon. check with LCRC's #741 & 768.

<u>LCRC #3002</u>	Nail & tag 16" Pine	N20°W	71.17'	<u>LCRC #4962</u>	Nail & Remon. tag E. side 18" Pine	N20°W	71.17'
	Nail & tag CP Pole	S00°W	63.03'		Nail & Remon. tag W. side CP Pole	S00°W	63.03'
	Nail & tag 12" Elm	S55°W	129.21'		Nail & Remon. tag N. side 18" Elm	S55°W	129.21'
					Nail & Remon. tag N. side 12" Elm	S80°W	137.50'
					Nail & Remon. tag S. side 8" Ash	N50°E	43.29'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Standard Kent County Monument

New Nail & KC Remon. tag E. side 18" Pine	N20°W	71.31'
Nail & KC Remon. tag W. side CP Pole	S00°W	63.05'
New Nail & KC Remon. tag N. side 24" Elm	S55°W	129.28'
New Nail & KC Remon. tag N. side 16" Elm	S80°W	137.63'
Nail & KC Remon. tag S. side 8" Ash	N50°E	43.35'



Signed by *Wm R. Byl*  
 Surveyor's Michigan License No. 23502

Date 11/27/94