

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -5 AM 8:59

W. R. Byl
 REG. OF DEEDS

7689

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>J-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|---------|------------------|---------|--------------------------|
| J-13 | 1831 | GLO | Mullett | Set Post |
| | 1956-61 | Williams & Works | | Boat Spike |
| | 1963 | Kent Co. Wit. | | Iron |
| | 1983 | LCRC #3481 | Byl | Set Kent County Monument |
| | 1989 | LCRC #4963 | Bueche | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 4/22/83 and was recorded per LCRC #3481

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1" Iron Pipe he found 0.15' West of a 3/4" Iron Pipe. Said 1" Iron Pipe checks with Williams & Works, Kent Co. Wit. and the Twp. jog better than the 3/4" Iron Pipe.

- | | |
|------------------------------------|------------------------------|
| <u>LCRC #3481</u> | <u>LCRC #4963</u> |
| Nail & tag 24" Maple N60°W 68.27' | same witnesses as LCRC #3481 |
| Nail & tag MBT Pole S15°E 33.85' | |
| Nail & tag 16" Willow S55°E 60.13' | |
| Nail & tag 16" Ash N75°E 100.13' | |
| KC Mon. N 1/4 2-5-11 N90°E 13.10' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-13 Standard Kent County Monument
- | | | |
|--|-------|---------|
| Nail & KC Remon. tag N. side 26" Maple | N60°W | 68.27' |
| Nail & KC Remon. tag W. side MBT Pole | S15°E | 33.85' |
| New Nail & KC Remon. tag S. side 18" Ash | N75°E | 100.05' |
| Set Nail & KC Remon. tag W. side 10" Maple | N05°W | 28.22' |
| Set Nail & KC Remon. tag N. side 16" Elm | S50°E | 61.73' |
| KC Mon. at N 1/4 cor. Sec. 2-5-11 | N90°E | 13.10' |



Signed by *W. R. Byl*
 Surveyor's Michigan License No. 23502

Date 11/27/94