

# SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 8:59

*Lucy Bond*  
REG. OF DEEDS

For corners in  
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	R	11W	K-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

7690

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-1	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1941	Kent Co. Wit.		1" Iron	PEER APPROVED 12/1/99
	1972	LCRC #360	Bonnema	1/2" Iron	CHAIRMAN <i>Harry Huber</i>
	1982	LCRC #3163	Stadt	Set Kent County Monument	
	1991	LCRC #5728	Bueche	Reset Kent County Monument after const.	
	1991	LCRC #6376	Marschall	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 11/29/82 and was recorded per LCRC #3163

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche at the same location as set in 1982 by Russell E. Stadt in place of the 1/2" Iron he found. Said 1/2" Iron checks with Kent Co. Wit. and LCRC #360.

LCRC #3163

LCRC #6376

Nail & tag P. Pole	N50°W	56.82'	Nail & tag W. side 48" Oak	N80°W	63.88'
Nail & tag P. Pole	N45°E	57.64'	Nail & tag N. side 8" Crab Apple	S55°W	57.18'
Nail & tag 12" Pine	S40°W	44.86'	Nail & tag SW side Util. Pole	N52°W	56.65'
Nail & tag 6" Pine	S85°W	24.85'	Nail & tag NW side Util. Pole	N36°E	57.62'
Nail & tag 16" Pine	S25°W	83.10'	Nail & tag S. side Util. Pole	N88°E	34.25'

C/L blktp. rd. N-S is 3' E.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Standard Kent County Monument

New Nail & KC Remon. tag W. side 48" Oak	N80°W	63.88'
Nail & KC Remon. tag N. side 8" Crab Apple	S55°W	57.25'
Nail & KC Remon. tag SW side Util. Pole	N52°W	56.65'
Nail & KC Remon. tag NW side Util. Pole	N36°E	57.62'
Nail & KC Remon. tag S. side Util. Pole	N88°E	34.25'
NE cor. 5" plastic light pole	S30°W	59.12'
C/L blktp. rd. N-S is 2' E.; Tree row to W is 9' N.		



Signed by \_\_\_\_\_

Date 11/27/94

Surveyor's Michigan License No. 23502