

**SURVEY & REMONUMENTATION**

APR 27 1995

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 DEC -5 AM 9:00

*Leif J. Bond*  
REG. OF DEEDS

For corners in  
**COMMISSION**  
**KENT COUNTY**  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7695

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Sept. 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-6	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		1/2" Iron
	1974	LCRC #694	Bonnema	1/2" Iron
	1981	LCRC #2028	Hackbardt	Set Kent County Monument
	1989	LCRC #4967	Bueche	Kent County Monument
	1993	LCRC #6754	Roon	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/1/94  
CHAIRMAN Gary Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 6/10/81 and was recorded per LCRC #2028

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 1/2" x 6" Bt. Spike over a 1/4" x 6" conc. nail over a 1/2" x 18" Iron he found. All check with Kent Co. Wit. and LCRC #694.

LCRC #2028		LCRC #4967 & #6754	
C/L Hydrant	N75°W 78.86'	C/L hydrant	N75°W 78.86'
C/L Manhole	N60°W 46.12'	C/L manhole	N60°W 46.12'
Nail & cap 30" Maple	N45°E 65.90'	Nail & tag 36" Maple	N45°E 65.90'
Nail & cap Tri. 12" Spruce	S40°E 52.92'	Nail & tag 26" Maple	N80°E 36.85'
		Nail & tag 16" Fir	S40°E 52.83'
		Nail & tag P. Pole	S45°W 36.84'
		Nail & tag P. Pole	N60°W 81.44'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Standard Kent County Monument			
C/L Hydrant	N75°W	78.82'	
C/L Manhole	N60°W	46.12'	
Nail & KC Remon. tag S. side 36" Maple	N45°E	65.96'	
New Nail & KC Remon. tag N. side 26" Maple	N80°E	36.85'	
New Nail & KC Remon. tag SW side 16" Fir	S40°E	52.80'	
Nail & KC Remon. tag P. Pole	S45°W	36.89'	
Nail & KC Remon. tag P. Pole	N60°W	81.40'	



Signed by *William R. Byl*  
Surveyor's Michigan License No. 23502

Date 23502