

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 9:00

W. R. Byl
REG. OF DEEDS

7698

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>K-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Sept. 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Mon. Box
	1973	LCRC #433	VanKooten	1/2" Iron
	1973	LCRC #527	Bonnema	1/2" Iron in mon. box
	1981	LCRC #2032	Hackbardt	Set Kent County Monument in mon. box
	1984	LCRC #3952	Bonnema	Found PK Nail @ edge MH rim
	1989	LCRC #4970	Bueche	PK Nail @ edge MH rim
	1993	LCRC #6750	Roon	PK Nail @ edge MH rim

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Thuermer*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 7/6/81 and was recorded per LCRC #2032

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found PK Nail at Easterly edge of MH rim per witnesses from above LCRC as found by Douglas W. Bonnema. Said PK Nail checks with previous measurement and angles in adjoining sections. (most of witnesses from LCRC #2032 removed during road const.)

<u>LCRC #3952</u>		<u>LCRC #6750</u>	
C/L Hydrant	S30°E 81.37'	Nail & tag in P. Pole	S10°E 80.86'
C/L Manhole	South 69.43'	Nail & tag in P. Pole	S55°W 74.45'
Exxel Iron at walk-curb	N36°E 58.88'	Nail & tag top guard rail post	N35°E 60.27'
Exxel Iron at walk-curb	S40°E 66.80'		
Capped Exxel Iron on S/L	West 25.00'		
SE cor. brick bldg.	N24°W 175.12'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 PK Nail at Easterly edge of MH rim	
C/L Hydrant	S30°W 81.39'
C/L Manhole	S00°E 69.46'
SE cor. brick bldg.	N24°W 175.08'
Nail & MDSH tag in P. Pole	S10°E 81.60'
Nail & KC Remon. tag in P. Pole	S50°W 74.52'
Set Nail & KC Remon. tag top guard rail post	N35°E 61.86'
"X" cut on MH rim	N00°E 0.45'



Signed by *W. R. Byl*

Date 112794

Surveyor's Michigan License No. 23502