

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -5 AM 9:00

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>K-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

W. R. Byl
REG. OF DEEDS

7701

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Sept. 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12	1831	GLO	Mullett	Set Post
	1952	Kent Co. Wit.		1" Iron in mon. box
	1979	LCRC #1301	Bonnema	Iron in mon. box
	1982	LCRC #2997	Byl	Set Kent County Monument in mon. box
	1989	LCRC #4973	Bueche	Kent County Monument in mon. box
	1993	LCRC #6765	Roon	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/19/82 and was recorded per LCRC #2997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1/2" x 18" Iron he found over a 1 1/2" Iron Pipe inside a mon. box. Both Irons check with Kent Co. Wit. and LCRC #1301.

LCRC #2997

LCRC #6765

Nail & tag 12" Hickory	N85°E	40.78'	Nail & tag fence post	West	42.75'
Nail & tag 6" Hickory	S40°E	99.57'	Nail & tag 10" Ash	N50°W	40.34'
SE brick hse. cor.	N65°W	135.90'	Nail & tag 20" Tw. Hickory	East	40.94'
SW cor. brick planter	N85°E	106.81'	Nail & tag 11" Maple	N45°E	84.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument		
Nail & MDSH tag in fence post	S90°W	42.85'
Nail & KC Remon. tag NE side 10" Ash	N50°W	40.42'
SE cor. brick face hse. #5591	N65°W	135.86'
SW cor. hse. fnd. #5592	N85°E	108.96'
Set Nail & KC Remon. tag NW side P. Pole	S45°W	91.72'
Set Nail & KC Remon. tag NE side P. Pole	S40°E	68.68'



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 112794