

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -5 AM 9:00

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|--------------------------|-------------|-------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>K-13</u> | |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

W. R. Byl
REG. OF DEEDS

7702

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|------|------|---------------|---------|--------------------------------------|--|
| K-13 | 1831 | GLO | Mullett | Set Post | |
| | | Kent Co. Wit. | | Iron | |
| | 1983 | LCRC #3222 | Bonnema | 1" Iron in mon. box | |
| | 1983 | LCRC #3482 | Byl | Set Kent County Monument in mon. box | |
| | 1989 | LCRC #4974 | Bueche | Kent County Monument in mon. box | |
| | 1993 | LCRC #6765 | Roon | Kent County Monument | |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *W. R. Byl*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 7/25/83 and was recorded per LCRC #3482

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl over the 1 1/4" Iron he found inside a mon. box. Said Iron in mon. box checks with Kent Co. Wit. and LCRC #3222.

<u>LCRC #3482</u>	<u>LCRC #6765</u>
Nail & tag P. Pole S50°E 105.95'	Nail & tag T.P. N45°E 36.50'
Nail & tag Lt. Pole S45°E 36.78'	Top C/L fire hydrant N75°E 51.18'
Nail & tag MBT Pole N45°W 97.26'	Top C/L fire hydrant S20°E 94.18'
Nail & tag MBT Pole N25°E 111.64'	KC Mon. (K-1, T5N, R11W) East 27.05'
NW cor. Sec. 1-5-11 (KC Mon.) East 27.08'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---------------|
| K-13 Standard Kent County Monument in mon. box | |
| New Nail & KC Remon. tag in Lt. Pole | N45°E 36.51' |
| Top C/L fire hydrant (different location) | N75°E 74.30' |
| Top C/L fire hydrant | S20°E 94.15' |
| Set Nail & KC Remon. tag NW side 14" Elm | S50°W 100.41' |
| Top C/L MBT box | N50°W 47.75' |
| KC Mon. (K-1, T5N, R11W) | S90°E 27.05' |



Signed by *W. R. Byl*

Date 112794

Surveyor's Michigan License No. 23502