

**SURVEY & REMONUMENTATION**

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 94 DEC -5 AM 9:00  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in  
**KENT COUNTY**  
(County)

Located In:

Corner Code: #

*W. R. Byl*  
REG. OF DEEDS

1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7703

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Sept. 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-1	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1972	LCRC #360	Bonnema	Set "T" Post from plat data
	1982	LCRC #3164	Stadt	Set Kent County Monument
	1991	LCRC #6374	Marschall	Kent County Monument under 12" of water

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/11/94  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 11/22/82 and was recorded per LCRC #3164

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the "T" Post he found. Said "T" Post checks with LCRC #360.

<u>LCRC #3164</u>	<u>LCRC #6374</u>
Nail & tag Trip. 16" Ash East	43.75' same witnesses as LCRC #3164
Nail & tag 12" W. Cherry N10°W	55.42'
Nail & tag 4" Oak S80°W	15.71'
Nail & tag 30" Oak N80°W	33.63'
C/L manhole N50°E	21.57'
C/L drain running West is 15' North	
C/L drain running N-S is East 5'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument at edge of drain under 12" of water	
New Nail & KC Remon. tag S. side Trip. 18" Ash	S90°E 44.62'
Nail & KC Remon. tag E. side 12" W. Cherry (dead)	N10°W 55.39'
New Nail & KC Remon. tag S. side 6" Oak	S80°W 15.71'
New Nail & KC Remon. tag S. side 36" Oak	N80°W 33.63'
Fd. Nail & KC Remon. tag NE side 12" Poplar	S50°E 17.50'
Fd. Nail & KC Remon. tag N. side 12" Oak	N65°W 9.00'
C/L manhole	N50°E 21.47'
C/L drain running West is 15' North	
C/L drain running N-S is East 5'	



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11/27/94